


POST SHALL BE JOINED AS SHOWN, THEN ROTATED 180° IN DIRECTION SHOWN AND DRIVEN INTO THE GROUND.

SILT FENCE JOINTS



PREASSEMBLED SILT FENCE

INSTALLATION NOTES:

1. DRIVE POSTS VERTICALLY INTO THE GROUND TO A MINIMUM DEPTH OF 18".
2. EXCAVATE A TRENCH APPROXIMATELY 4" WIDE AND 4" DEEP ALONG THE LINE OF POSTS AND UPSLOPE FROM THE BARRIER.
3. ANCHOR TRENCH SHALL BE EXCAVATED BY HAND, WITH TRENCHER, OR WITH SILT FENCE INSTALLATION MACHINE. NO ROAD GRADERS, BACKHOES, ETC. SHALL BE USED.
4. NOT LESS THAN THE BOTTOM 1' OF THE SILT FENCE FABRIC SHALL BE BURIED IN THE TRENCH.
5. THE TRENCH SHALL BE COMPACTED BY HAND, WITH "JUMPING JACK" OR BY WHEEL ROLLING. COMPACTION SHALL BE SUCH THAT THE SILT FENCE RESISTS BEING PULLED OUT OF ANCHOR TRENCH BY HAND.
6. SILT FENCE INDICATED IN THE PLANS SHALL BE INSTALLED PRIOR TO ANY LAND-DISTURBING ACTIVITIES.
7. USE WOOD POSTS OR OTHER MATERIAL AS ACCEPTED BY THE CITY.

MAINTENANCE NOTES:

1. THE CONTRACTOR SHALL INSPECT SILT FENCE EVERY TWO WEEKS AND AFTER SIGNIFICANT STORM EVENTS AND MAKE REPAIRS OR CLEAN OUT UPSTREAM SEDIMENT AS NECESSARY. SEDIMENT ACCUMULATED UPSTREAM OF SILT FENCE SHALL BE REMOVED WHEN THE SEDIMENT REACHES A DEPTH OF 6".
2. UPSTREAM SEDIMENT REACHES A DEPTH OF 6".
3. SILT FENCE SHALL BE REMOVED WHEN THE UPSTREAM DISTURBED AREA IS STABILIZED AND GRASS COVER IS ACCEPTED BY THE CITY. IF ANY DISTURBED AREA EXISTS AFTER REMOVAL, IT SHALL BE SEEDED AND MULCHED OR OTHERWISE STABILIZED IN A MANNER ACCEPTED BY THE CITY.

<b>SILT FENCE</b>		(SF) ——— SF ——— SF ———
 <p>CITY OF LOVELAND PUBLIC WORKS DEPT. STORMWATER</p>	<p>STORMWATER CONSTRUCTION DRAWINGS</p>	<p>APPROVED: KWG</p>
		<p>DATE: 8/17/07</p>
		<p>DRAWN BY: TBK</p>
		<p>DRAWING SW-10</p>